
			1		
Test No.	Speed (mph)	Special Note			
RDLT-1	50	Hit Brakes at End of Rip Rap			
traje		Concrete barriers as reto shield cable system fence/property. Soft tarmac Rip Rap 107' [393] Concrete barriers as reto shield cable system fence/property.	and airport	Potential window of vehicle bra run out. Relatively flat, native in no hazard.	king soil,
- Braking Regi	on		MWRSE	WI RIP RAP ROCK DITCH LINER	1 of 3 DATE:
Notes: (1) Layout No	. 1.			POTENTIAL LAYOUT — 1	5/26/2015 DRAWN BY:
	ncrete barriers as nec em and airport fence		Midwest Roadside Safety Facility	DWG. NAME. SCALE: 1:50 WI Rip Rap_R5.dwg UNITS: ft.[m	

Test No.	Speed (mph)	Special Note	
RDLT-1	50	Hit Brakes at End of Rip Rap	
		193' [706] Concrete barriel to shield cable	rs as necessary system and airport



Legend



Rip Rap



Braking Region

Notes: (1) Alternative Layout No. 2.

(2) Install concrete barriers as necessary to shield cable system and airport fence/property.



Midwest Roadside Safety Facility

WI RIP RAP ROCK DITCH LINER 2 of 3 DATE: 5/26/15


SHEET:

POTENTIAL LAYOUT - 2

DRAWN BY: ALL

DWG. NAME. WI Rip Rap_R5.dwg SCALE: 1:500 REV. BY:

UNITS: ft.[m] KAL/CSS /RKF



PROFILE VIEW

Notes: (1) Rip rap can extend a maximum of 6" [152] above ground. It should not be smooth. It should be made as rough as possible.

- (2) Primarily use 10-12 in. diameter rocks dumped from truck into trench. Fill gaps by dumping rocks less than or equal to 6 in. on top. Do not smooth. Limit rocks to max of 6" above grade.
- (3) GoPros (or equivalent) should be used within the vehicle suspension along with transducers installed on lower/upper control arms identical to NSRI project (test nos. SH-1 through SH-3, SC-1, and ST-1).
- (4) Test vehicle should be a 4-door Yaris (sedan-type), around 2010 model.
- (5) Vehicle can be on or off. Desire to also collect ACM data.
- (6) Vehicle's initial contact with the rock ditch liner should involve one wheel impacting before the other.
- (7) Braking should be initiated approximately when the vehicle leaves the end of the rip rap if considerable speed remains after traversing rock ditch liner.

-Rip Rap Specification/Installation Primarily use 10—12 in. diameter rocks dumped from truck into trench.

Fill gaps by dumping rocks less than or equal to 6 in. on top.

- *Do not smooth.
- *Limit rocks to max of 6" above grade.
- *Rocks are quasi-prismatic.



WI RIP RAP ROCK DITCH LINER

3 of 3 DATE: 5/21/2015

SHEET:

Midwest Roadside Safety Facility Rip Rap Detail

DRAWN BY: ALL

DWG. NAME.
WI Rip Rap_R5.dwg

SCALE: 1:7 UNITS: ft.[m]

REV. BY: KAL/CSS /RKF System: WI Rip Rap Rock Ditch Liner

Drawing: WI Rip Rap

Revision History

REV.	DATE OF ISSUE	Page	NATURE OF CHANGES	REVIEWER	REVISED BY
0	4/15/2015	_	Created drawing from sample—riprap—layout——2015—04—14.dwg		ALL
1	4/17/2015	-	Added leaders; changed font sizes; added note (2); fixed dimesion and annotation styles;	KAL	ALL
2	4/23/2015	3	Added page 3; section view of rip rap rock; added notes for testing	KAL	ALL
3	4/24/2015	1	Changed annotations	KAL	ALL
		2	Changed annotations		
		3	Fixed notes		
4 5/14		1	Changed barrier notations, added legend, changed note wording.		ALL
	5/14/2015	2	Changed barrier notations, added legend, changed note wording.	KAL/RKF /CSS	
		3	Re—drew profile view to reflect realistic look, added specifications and installation instructions to annotation and notes, made edits to notes.	/033	
5	5/21/2015	Changed rock height dimension to 6" max, added to note 5, replaced rock ditch liner with rip rap in note 7, added note to specification/installation.		CSS	ALL
	5/26/2015	1	Changed dimension points and added more dimensions		
6		2 Changed dimension points and added more dimensions RKF		RKF/KAL	ALL
		3	Added small fill rocks; made edits to notes		